Bruhat Bangalore Mahanagara Palike
Executive Engineer Byatarayanapura Division

Name of Work: Improvements to Roads And Drains at Palannahalli Chokkanahalli Vinayakanagara Dwarakanagara and Surrounding area in ward No-05 Byatarayanapura Sub Division Package-01

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
1	KSRRB300-1. Earthwork excavation by manual means for Drains and similar works in ordinar soil excavated surface levelled and sides neatly dressed, the dispossed earth to be levelled neatly after breaking of clods completed as per specifications.								
	Desilting	**Cum**							
	Shivpura Layout								
	Kanti Sweets Road		2.00	224.00	0.60	0.35	94.08		
	2nd Main Road Near Hindustan Hardware		2.00	230.00	0.60	0.35	96.60		
	Cross Road-1		2.00	130.00	0.60	0.35	54.60		
	Cross Road-2		2.00	180.00	0.60	0.35	75.60		
	Shivpura Layout								
	6th Cross Road		2.00	138.00	0.60	0.35	57.96		
	5th 'A' Cross Road		2.00	170.50	0.60	0.35	71.61		
	5th 'B' Cross Road		2.00	60.00	0.60	0.35	25.20		
	4th 'A' Cross Road		2.00	145.00	0.60	0.35	60.90		
	4th 'B' Cross Road		2.00	65.00	0.60	0.35	27.30		
	3rd 'A' Cross Road		2.00	50.00	0.60	0.35	21.00		
	3rd 'B' Cross Road		2.00	70.00	0.60	0.35	29.40		
	2nd 'A' Cross Road		2.00	47.00	0.60	0.35	19.74		
	2nd 'B' Cross Road		2.00	220.00	0.60	0.35	92.40		
	1st 'A' Cross road		2.00	52.00	0.60	0.35	21.84		
	1st 'B' Cross Road		2.00	210.00	0.60	0.35	88.20		
	Srinivasa Hotel Road		2.00	65.00	0.60	0.35	27.30		
	Someshawara Layout								
	Sri Siddeshawara General Store Road		2.00	75.00	0.60	0.35	31.50		
	Sri Ramanginaiya Nilaya # 9		2.00	130.00	0.60	0.35	54.60		
	Gangothri Badavani								
	1st Cross Road		2.00	50.00	0.60	0.30	18.00		
	2nd Cross Road		2.00	70.00	0.60	0.30	25.20		
	3rd Cross Road		2.00	100.00	0.60	0.30	36.00		
	Cross Road		2.00	65.00	0.60	0.30	23.40		
	Main Road		2.00	70.00	0.60	0.30	25.20		
	Poojappa Layout								
	4th Cross Road		2.00	350.00	0.60	0.35	147.00		
	Muneshawara Swamy General Store		2.00	100.00	0.60	0.35	42.00		
	Kempegowda Layout								
	Main Road		2.00	185.00	0.60	0.35	77.70		
	1st Main Road		2.00	142.00	0.60	0.35	59.64		
	Cross Road-5		2.00	65.00	0.60	0.35	27.30		
	1st Cross Left Side Of Main Road		2.00	90.00	0.60	0.35	37.80		
	2nd Cross Left Side Of Main Road		2.00	88.00	0.60	0.35	36.96		
	3rd Cross Left Side Of Main Road		2.00	92.00	0.60	0.35	38.64		
	Cross Road End		2.00	218.00	0.60	0.35	91.56		
	Arogya Hospital beside Rood		2.00	490.50	0.60	0.35	206.01		
	M.C.E.C.H.S Layout								
	1st Cross Road		2.00	182.00	0.60	0.35	76.44		
	2nd Cross Road		2.00	190.00	0.60	0.35	79.80		
	3rd Cross Road		2.00	200.00	0.60	0.35	84.00		
	4th Cross Road		2.00	200.00	0.60	0.35	84.00		
	5th Cross Road		2.00	205.00	0.60	0.35	86.10		
	6th Cross Road		2.00	210.00	0.60	0.35	88.20		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Cross Road		2.00	212.00	0.60	0.35	89.04		
8th Cross Road		2.00	215.00	0.60	0.35	90.30		
Cross Road-4 Bilal Imam #103/17		2.00	195.00	0.60	0.35	81.90		
Cross Road -3 Guru Krupa # 40		2.00	95.00	0.60	0.35	39.90		
Cross Road -2		2.00	56.00	0.60	0.35	23.52		
Cross Road-1		2.00	95.00	0.60	0.35	39.90		
Dutta town ship								
2nd Cross Road SreeKaram Nilaya		2.00	40.00	0.60	0.35	16.80		
Cross Road-1		2.00	160.00	0.60	0.35	67.20		
Cross Road-2		2.00	120.00	0.60	0.35	50.40		
Cross Road at End		2.00	270.00	0.60	0.35	113.40		
Cross Road -3 Right side		2.00	140.00	0.60	0.35	58.80		
Cross Road-4 Right side		2.00	118.00	0.60	0.35	49.56		
Cross Road-5 right side		2.00	86.00	0.60	0.35	36.12		
Cross Road-6 right side		2.00	52.00	0.60	0.35	21.84		
Agrahara Layout Main Road		2.00	240.00	0.60	0.35	100.80		
Thirumenahalli (Ward No-05)								
1st Cross Road		2.00	101.00	0.60	0.30	36.36		
2nd Cross Road		2.00	155.00	0.60	0.30	55.80		
MVM Sumo Institution Road		2.00	50.00	0.60	0.30	18.00		
Balaji Layout								
Pristine Woods Apartments		2.00	150.00	0.60	0.35	63.00		
Main Road		2.00	295.00	0.60	0.35	123.90		
1st Cross road Left side		2.00	87.00	0.60	0.35	36.54		
2nd Cross road Left side		2.00	50.00	0.60	0.35	21.00		
3rd Cross road Left side		2.00	65.00	0.60	0.35	27.30		
2nd Cross Road Right side		2.00	65.00	0.60	0.35	27.30		
1st Cross Road Right side		2.00	60.00	0.60	0.35	25.20		
3rd Cross Road Right		2.00	58.00	0.60	0.35	24.36		
Cross Road		2.00	31.00	0.60	0.35	13.02		
4th Cross Right Side		2.00	50.00	0.60	0.35	21.00		
Kattigenahalli Main Road		2.00	860.00	0.60	0.35	361.20		
Cross Road		2.00	336.00	0.60	0.35	141.12		
Kattigenahalli Surrounding								
1st Cross Road		2.00	185.00	0.60	0.35	77.70		
Cross Road-2		2.00	180.00	0.60	0.35	75.60		
Cross Road-3		2.00	225.00	0.60	0.35	94.50		
Cross Road-4		2.00	240.00	0.60	0.35	100.80		
Cross Road-5		2.00	180.00	0.60	0.35	75.60		
Cross Road-6		2.00	243.00	0.60	0.35	102.06		
Basavalingappa Nagar								
Main Road		2.00	318.00	0.60	0.35	133.56		
1st Cross Road		2.00	200.00	0.60	0.35	84.00		
2nd Cross Road		2.00	160.00	0.60	0.35	67.20		
3rd Cross Road		2.00	168.00	0.60	0.35	70.56		
Kanti Sweets Road		2.00	254.00	0.60	0.35	106.68		
W Drive way road		2.00	230.00	0.60	0.35	96.60		
7th Cross Road		2.00	220.00	0.60	0.35	92.40		
Reva College Road		2.00	250.00	0.60	0.35	105.00		
1st Cross Road		2.00	60.00	0.60	0.35	25.20		
2nd Cross Road		2.00	60.00	0.60	0.35	25.20		
3rd Cross Road		2.00	60.00	0.60	0.35	25.20		
4th Cross Road		2.00	60.00	0.60	0.35	25.20		
5th Cross Road		2.00	60.00	0.60	0.35	25.20		
6th Cross Road		2.00	65.00	0.60	0.35	27.30		
7th Cross Road		2.00	65.00	0.60	0.35	27.30		
Olive Plant Road		2.00	280.00	0.60	0.35	117.60		
Cross Road		2.00	212.00	0.60	0.35	89.04		
Cross Road-1		2.00	180.00	0.60	0.35	75.60		

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	oss Road-2								
	Cross Road-3		2.00	187.00	0.60	0.35	78.54		
	DMK Layout		2.00	240.00	0.60	0.35	100.80		
	Palanahalli Lake Surrounding		2.00	340.00	0.60	0.35	142.80		
	1st Cross Road								
	2nd Cross Road		2.00	235.00	0.60	0.30	84.60		
	3rd Cross Road		2.00	160.00	0.60	0.30	57.60		
	4th Cross Road		2.00	105.00	0.60	0.30	37.80		
	5th Cross Road		2.00	105.00	0.60	0.30	37.80		
	6th Cross Road		2.00	105.00	0.60	0.30	37.80		
	7th Cross Road		2.00	295.00	0.60	0.30	106.20		
	Kuvempu Nagar		2.00	200.00	0.60	0.30	72.00		
	Main Road								
	1st Cross Road		2.00	500.00	0.60	0.30	180.00		
	2nd Cross Road		2.00	175.00	0.60	0.30	63.00		
	3rd Cross Road		2.00	175.00	0.60	0.30	63.00		
	4th Cross Road		2.00	175.00	0.60	0.30	63.00		
	Someshawara Layout		2.00	155.00	0.60	0.30	55.80		
	Main Road								
	1st Cross Road		2.00	258.00	0.60	0.30	92.88		
	2nd Cross Road		2.00	240.00	0.60	0.30	86.40		
	M.C.E.C.H.S Layout		2.00	60.00	0.60	0.30	21.60		
	1st Cross road								
	2nd Cross road		1.00	6.00	1.40	0.80	6.72		
	3rd Cross road		1.00	6.00	1.40	0.80	6.72		
	4th Cross road		1.00	6.00	1.40	0.80	6.72		
	5th Cross road		1.00	6.00	1.40	0.80	6.72		
	6th Cross road		1.00	6.00	1.40	0.80	6.72		
	Basavalingapura		1.00	6.00	1.40	0.80	6.72		
	Masjid Road								
	New Culverts		1.00	5.50	1.40	0.80	6.16		
	Shivshankar Layout								
	1st Main Road								
	2nd Main Road		1.00	7.00	1.50	0.90	9.45		
	Dutta Town Ship		1.00	7.10	1.50	0.90	9.59		
	Main road								
	Basavalingapura		1.00	6.80	1.50	0.90	9.18		
	Cross Road								
			1.00	19.00	1.50	0.90	25.65		
	Approved rate	**213.9079**					**7441.99**	**213.9079**	**1591900.45**
2	Removing & Refixing Stone slabs of drains and pointing in CM (1:3) Complete as per specification and direction of the engineer in-charge of the work.								
		Sqm							
	Shivpura Layout								
	Kanti Sweets Road		2.00	224.00	1.35		604.80		
	2nd Main Road Near Hindustan Hardware		2.00	230.00	1.35		621.00		
	Cross Road-1		2.00	130.00	1.35		351.00		
	Cross Road-2		2.00	180.00	1.35		486.00		
	Shivpura Layout								
	6th Cross Road		2.00	138.00	1.35		372.60		
	5th 'A' Cross Road		2.00	170.50	1.35		460.35		
	5th 'B' Cross Road		2.00	60.00	1.35		162.00		
	4th 'A' Cross Road		2.00	145.00	1.35		391.50		
	4th 'B' Cross Road		2.00	65.00	1.35		175.50		
	3rd 'A' Cross Road		2.00	50.00	1.35		135.00		
	3rd 'B' Cross Road		2.00	70.00	1.35		189.00		
	2nd 'A' Cross Road		2.00	47.00	1.35		126.90		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
2nd 'B' Cross Road		2.00	220.00	1.35		594.00		
1st 'A' Cross road		2.00	52.00	1.35		140.40		
1st 'B' Cross Road		2.00	210.00	1.35		567.00		
Srinivasa Hotel Road		2.00	65.00	1.35		175.50		
Someshawara Layout								
Sri Siddeshawara General Store Road		2.00	75.00	1.35		202.50		
Sri Ramanginaiya Nilaya # 9		2.00	130.00	1.35		351.00		
Gangothri Badavani								
1st Cross Road		2.00	50.00	1.35		135.00		
2nd Cross Road		2.00	70.00	1.35		189.00		
3rd Cross Road		2.00	100.00	1.35		270.00		
Cross Road		2.00	65.00	1.35		175.50		
Main Road		2.00	70.00	1.35		189.00		
Poojappa Layout								
4th Cross Road		2.00	350.00	1.35		945.00		
Muneshawara Swamy General Store		2.00	100.00	1.35		270.00		
Kempegowda Layout								
Main Road		2.00	185.00	1.35		499.50		
1st Main Road		2.00	142.00	1.35		383.40		
Cross Road-5		2.00	65.00	1.35		175.50		
1st Cross Left Side Of Main Road		2.00	90.00	1.35		243.00		
2nd Cross Left Side Of Main Road		2.00	88.00	1.35		237.60		
3rd Cross Left Side Of Main Road		2.00	92.00	1.35		248.40		
Cross Road End		2.00	218.00	1.35		588.60		
Arogya Hospital beside Rood		2.00	490.50	1.35		1324.35		
M.C.E.C.H.S Layout								
1st Cross Road		2.00	182.00	1.35		491.40		
2nd Cross Road		2.00	190.00	1.35		513.00		
3rd Cross Road		2.00	200.00	1.35		540.00		
4th Cross Road		2.00	200.00	1.35		540.00		
5th Cross Road		2.00	205.00	1.35		553.50		
6th Cross Road		2.00	210.00	1.35		567.00		
7th Cross Road		2.00	212.00	1.35		572.40		
8th Cross Road		2.00	215.00	1.35		580.50		
Cross Road-4 Bilal Imam #103/17		2.00	195.00	1.35		526.50		
Cross Road -3 Guru Krupa # 40		2.00	95.00	1.35		256.50		
Cross Road -2		2.00	56.00	1.35		151.20		
Cross Road-1		2.00	95.00	1.35		256.50		
Dutta town ship								
2nd Cross Road SreeKaram Nilaya		2.00	40.00	1.35		108.00		
Cross Road-1		2.00	160.00	1.35		432.00		
Cross Road-2		2.00	120.00	1.35		324.00		
Cross Road at End		2.00	270.00	1.35		729.00		
Cross Road -3 Right side		2.00	140.00	1.35		378.00		
Cross Road-4 Right side		2.00	118.00	1.35		318.60		
Cross Road-5 right side		2.00	86.00	1.35		232.20		
Cross Road-6 right side		2.00	52.00	1.35		140.40		
Agrahara Layout Main Road		2.00	240.00	1.35		648.00		
Thirumenahalli (Ward No-05)								
1st Cross Road		2.00	101.00	1.35		272.70		
2nd Cross Road		2.00	155.00	1.35		418.50		
MVM Sumo Institution Road		2.00	50.00	1.35		135.00		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Balaji Layout								
Pristine Woods Apartments		2.00	150.00	1.35		405.00		
Main Road		2.00	295.00	1.35		796.50		
1st Cross road Left side		2.00	87.00	1.35		234.90		
2nd Cross road Left side		2.00	50.00	1.35		135.00		
3rd Cross road Left side		2.00	65.00	1.35		175.50		
2nd Cross Road Right side		2.00	65.00	1.35		175.50		
1st Cross Road Right side		2.00	60.00	1.35		162.00		
3rd Cross Road Right		2.00	58.00	1.35		156.60		
Cross Road		2.00	31.00	1.35		83.70		
4th Cross Right Side		2.00	50.00	1.35		135.00		
Kattigenahalli Main Road		2.00	860.00	1.35		2322.00		
Cross Road		2.00	336.00	1.35		907.20		
Kattigenahalli Surrounding								
1st Cross Road		2.00	185.00	1.35		499.50		
Cross Road-2		2.00	180.00	1.35		486.00		
Cross Road-3		2.00	225.00	1.35		607.50		
Cross Road-4		2.00	240.00	1.35		648.00		
Cross Road-5		2.00	180.00	1.35		486.00		
Cross Road-6		2.00	243.00	1.35		656.10		
Basavalingappa Nagar								
Main Road		2.00	318.00	1.35		858.60		
1st Cross Road		2.00	200.00	1.35		540.00		
2nd Cross Road		2.00	160.00	1.35		432.00		
3rd Cross Road		2.00	168.00	1.35		453.60		
Kanti Sweets Road		2.00	254.00	1.35		685.80		
W Drive way road		2.00	230.00	1.35		621.00		
7th Cross Road		2.00	220.00	1.35		594.00		
Reva College Road		2.00	250.00	1.35		675.00		
1st Cross Road		2.00	60.00	1.35		162.00		
2nd Cross Road		2.00	60.00	1.35		162.00		
3rd Cross Road		2.00	60.00	1.35		162.00		
4th Cross Road		2.00	60.00	1.35		162.00		
5th Cross Road		2.00	60.00	1.35		162.00		
6th Cross Road		2.00	65.00	1.35		175.50		
7th Cross Road		2.00	65.00	1.35		175.50		
Olive Plant Road		2.00	280.00	1.35		756.00		
Cross Road		2.00	212.00	1.35		572.40		
Cross Road-1		2.00	180.00	1.35		486.00		
Cross Road-2		2.00	187.00	1.35		504.90		
Cross Road-3		2.00	240.00	1.35		648.00		
DMK Layout		2.00	340.00	1.35		918.00		
Palanahalli Lake Surrounding								
1st Cross Road		2.00	235.00	1.35		634.50		
2nd Cross Road		2.00	160.00	1.35		432.00		
3rd Cross Road		2.00	105.00	1.35		283.50		
4th Cross Road		2.00	105.00	1.35		283.50		
5th Cross Road		2.00	105.00	1.35		283.50		
6th Cross Road		2.00	295.00	1.35		796.50		
7th Cross Road		2.00	200.00	1.35		540.00		
Kuvempu Nagar								
Main Road		2.00	500.00	1.35		1350.00		

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	1st Cross Road		2.00	175.00	1.35		472.50		
	2nd Cross Road		2.00	175.00	1.35		472.50		
	3rd Cross Road		2.00	175.00	1.35		472.50		
	4th Cross Road		2.00	155.00	1.35		418.50		
	Someshawara Layout								
	Main Road		2.00	258.00	1.35		696.60		
	1st Cross Road		2.00	240.00	1.35		648.00		
	2nd Cross Road		2.00	60.00	1.35		162.00		
							48589.20		
						Considering 15%	**6285.7**	**112.4130**	**706589.90**
	Approved rate	**112.4130**							
3	Removing and resetting of footpath slabs complete as per specification and direction of the engineer in-charge of the work								
		Sqm							
	Missing slabs								
			1.00	10.00	0.90		9.00		
			1.00	12.00	0.90		10.80		
			1.00	8.00	0.90		7.20		
			1.00	4.00	0.90		3.60		
			1.00	6.00	0.90		5.40		
			1.00	9.00	0.90		8.10		
			1.00	10.00	0.90		9.00		
	Basavalingappa Nagar								
	Main Road								
	RHS								
	Ch.0.00 to 30.0m		1.00	30.00	0.90		27.00		
	Ch.30.0 to 60.0m		1.00	30.00	0.90		27.00		
	Ch.60.0 to 90.0m		1.00	30.00	0.90		27.00		
	Ch.90.0 to 120.0m		1.00	30.00	0.90		27.00		
	Ch.120.0 to 150.0m		1.00	30.00	0.90		27.00		
	Ch.150.0 to 180.0m		1.00	30.00	0.90		27.00		
	Ch.180.0 to 210.0m		1.00	30.00	0.90		27.00		
	Ch.210.0 to 240.0m		1.00	30.00	0.90		27.00		
	Ch.240.0 to 270.0m		1.00	30.00	0.90		27.00		
	Ch.270.0 to 300.0m		1.00	30.00	0.90		27.00		
	Ch.300.0 to 318.0m		1.00	18.00	0.90		16.20		
							330.30	**210.9082**	**69662.98**
	Approved rate	**210.9082**							
4	Providing Granite Slabs of selected quality Roughly dressed and fixed in cement mortor (1:6) including fixing curing etc., complete 7.5 cms thick complete as per specification and direction of the engineer in-charge of the work.								
		Sqm							
	Shivapura Layout								
	Missing slabs/Damaged Slabs								
	6th Cross Road		1.00	35.00	1.35		47.25		
	5th 'A' Cross Road		1.00	40.00	1.35		54.00		
	5th 'B' Cross Road		1.00	38.00	1.35		51.30		
	3rd 'A' Cross Road		1.00	33.00	1.35		44.55		
	3rd 'B' Cross Road		1.00	35.00	1.35		47.25		
	2nd Cross 'A' Road		1.00	28.00	1.35		37.80		
	Muneshawara Nagar								
	4th 'C' Cross Road		1.00	16.00	1.35		21.60		
	3rd Main Road		1.00	13.40	1.35		18.09		
	Balaji Layout								
	Pristine Woods Apartments		1.00	29.50	1.35		39.83		
	Main Road		1.00	28.70	1.35		38.75		
	1st Cross road Left side		1.00	7.60	1.35		10.26		
	3rd Cross road Left side		1.00	11.90	1.35		16.07		
	Cross Road		1.00	13.60	1.35		18.36		
	Thirumenahalli (Ward No-05)								

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	1 Cross Road								
	2nd Cross Road		1.00	19.20	1.35		25.92		
	DMK Layout		1.00	33.60	1.35		45.36		
			1.00	134.00	1.35		180.90		
							697.11	**749.4200**	**522428.18**
	Approved rate	**749.4200**					✓	✓	✓
5	Plain cement concrete M10 mix with crushed stone aggregates 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing including cost of materials, labour,HOM completed as per specifications								
		Cum							
	New Culverts								
	Shivshankar Layout								
	1st Main Road		1.00	7.00	1.40	0.15	1.47		
	2nd Main Road		1.00	7.10	1.40	0.15	1.49		
	Dutta Town Ship								
	Main road		1.00	6.80	1.40	0.15	1.43		
	Basavalingapura								
	Cross Road		1.00	19.00	1.40	0.15	3.99		
	Vidya Nagar								
	3rd Main Road		1.00	7.50	1.40	0.15	1.58		
	Kategenahalli Village Vivekananda Circle Near M.K Provisional store		1.00	6.50	1.40	0.15	1.37		
	Telecom Layout		1.00	5.80	1.40	0.15	1.22		
	Cross Road		1.00	5.50	1.40	0.15	1.16		
	Main Road		1.00	5.60	1.40	0.15	1.18		
							14.69	**4524.3556**	**66462.78**
	Approved rate	**4524.3556**					✓	✓	✓
6	Providing and Constructing granite /trap/basalt size stone masonry in foundation with cement mortor and stone hammered dressed in courses not less than 20Cms high bond stones at 2m apart in each course including cost of materials. Labours HOM, curing complete as per specification and direction of the engineer in-Charge of the work.								
		Cum							
	M.C.E.C.H.S Layout								
	1st Cross road		1.00	6.00	0.45	0.45	1.22		
	2nd Cross road		1.00	6.00	0.45	0.45	1.22		
	3rd Cross road		1.00	6.00	0.45	0.45	1.22		
	4th Cross road		1.00	6.00	0.45	0.45	1.22		
	5th Cross road		1.00	6.00	0.45	0.45	1.22		
	6th Cross road		1.00	6.00	0.45	0.45	1.22		
	Vidya Nagar								
	3rd Main Road		2.00	7.50	0.60	1.00	9.00		
	Kategenahalli Village Vivekananda Circle Near M.K Provisional store		2.00	6.50	0.60	1.00	7.80		
	Telecom Layout		1.00	6.80	0.60	1.00	4.08		
							28.17	**4920.4776**	**138609.85**
	Approved rate	**4920.4776**					✓	✓	✓
7	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69Cum and fine aggregates @ 0.459 Cum machine mixed concrete laid in layers not exceeding 15 cms thick well compacted for coping including cost of all materials labour HOM Curing complete as per specifications and direction of the engineer in-charge of the work								
		Cum							
							0.00	**5655.9798**	**0.00**
	Approved rate	**5655.9798**					✓	✓	✓
8	Providing and laying in position plain/ Reinforced cement concrete M20 for sub structure/superstructure works, with cement @ 320kgs 20mm & down size graded granite metal course aggregates @ 0.69 Cum and fine aggregates @ 0.46cum Machine mix complete as per specification and direction in charge of the work								
		Cum							
	New Culverts								
	Raft								
	Shivshankar Layout								

https://accounts.bonlpgenie.com/...

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Main Road		1.00	7.00	1.20	0.20	1.68		
	2nd Main Road		1.00	7.10	1.20	0.20	1.70		
	Dutta Town Ship								
	Main road		1.00	6.80	1.20	0.20	1.63		
	Basavalingapura								
	Cross Road		1.00	19.00	1.20	0.20	4.56		
	Side Wall								
	Shivshankar Layout								
	1st Main Road		2.00	7.00	0.20	0.80	2.24		
	2nd Main Road		2.00	7.10	0.20	0.80	2.27		
	Dutta Town Ship								
	Main road		2.00	6.80	0.20	0.80	2.18		
	Basavalingapura								
	Cross Road		2.00	19.00	0.20	0.80	6.08		
	Raft								
	Vidya Nagar								
	3rd Main Road		1.00	7.50	1.50	0.23	2.59		
	Kategenahalli Village Vivekananda Circle Near M.K Provisional store		1.00	6.50	1.50	0.23	2.24		
	Telecom Layout		1.00	6.80	1.50	0.23	2.35		
	Cross Road		1.00	5.50	1.50	0.23	1.90		
	Main Road		1.00	5.60	1.50	0.23	1.93		
	Wall Concrete								
	Cross Road		1.00	5.50	0.25	0.90	1.24		
	Main Road		1.00	5.60	0.25	0.90	1.26		
	Ramp								
	Kategenahalli Village Vivekananda Circle Near M.K Provisional store		2.00	7.00	1.20	0.23	3.86		
							39.71	**5330.5174**	**211674.85**
							✓	✓	✓
	Approved rate	**5330.5174**							
9	KSRRB M2200-6. Providing TMT Bars Fe 500 steel reinforcement for RCC work including Straightening, cutting, bending, hooking, placing in position, lapping and/or welding whereever required, tying with binding wire and anchoring to the adjoining members whereever necessary completed as per design ans specification.								
		Tonnes					3.17		
	For Culverts 90Kgs/Cum						**3.17**	**73050.2500**	**231569.29**
							✓	✓	✓
	Approved rate	**73050.2500**							
10	Providing and fixing RCC precast cover slab of 250mm thick made out of CC 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.								
		Sqm							
	M.C.E.C.H.S Layout								
	1st Cross road		1.00	6.00	1.50		9.00		
	2nd Cross road		1.00	6.00	1.50		9.00		
	3rd Cross road		1.00	6.00	1.50		9.00		
	4th Cross road		1.00	6.00	1.50		9.00		
	5th Cross road		1.00	6.00	1.50		9.00		
	6th Cross road								
	Basavalingapura								
	Masjid Road		1.00	5.50	1.20		6.60		
	New Culverts								
	Shivshankar Layout								
	1st Main Road		1.00	7.00	1.20		8.40		
	2nd Main Road		1.00	7.10	1.20		8.52		
	Dutta Town Ship								
	Main road		1.00	6.80	1.20		8.16		
	Basavalingapura								
	Cross Road		1.00	19.00	1.20		22.80		
	Vidya Nagar								

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	d Main Road		1.00	7.50	1.50		11.25		
	Kategenahalli Village Vivekananda Circle Near M.K Provisional store		1.00	6.50	1.50		9.75		
	Telecom Layout		1.00	6.80	1.50		10.20		
	Cross Road		1.00	5.50	1.50		8.25		
	Main Road		1.00	5.60	1.50		8.40		
	Missing /Damaged Slabs								
	Kuvempu Layout								
	Main Road		1.00	8.50	1.50		12.75		
	2nd Cross Road		1.00	6.30	1.50		9.45		
	Basavalingappa Nagar								
	Main Road		1.00	9.30	1.50		13.95		
	Cross Road		1.00	6.80	1.50		10.20		
	Cross Road Near Mosque		1.00	5.90	1.50		8.85		
	Shivpura Layout								
	6th Cross Road		1.00	8.60	1.50		12.90		
	3rd Cross Road		1.00	5.50	1.50		8.25		
	Kuvempu Nagar		1.00	4.30	1.50		6.45		
							239.13	**5472.1800**	**1308562.40**
	Approved rate	**5472.1800**					✓	✓	✓
11	KSRRB M300-14.Excavation for roadwork in all types of soil by machinical means including cutting and loading to tippers, trimming bottomand sides slopes in accordance with requirments of lines grades and cross sections and transportations withn alead of 1.00km and complete as per specifications. MORTH Specification no.301 and 4kms lead for disposal								
	Vijay Nagar Layout	**Cum**							
	5th Main Road From Entrance		1.00	596.00	6.80	0.30	1215.84		
	4th Main Road From End		1.00	210.00	6.00	0.30	378.00		
	1st Cross Hasini Grand Appartment Road		1.00	136.00	5.50	0.30	224.40		
	2nd Cross M. Valarmathi Muniratnam #7		1.00	105.00	6.00	0.30	189.00		
	3rd Cross Sri Chowdeshawari Nilaya Laxmi Anjinappa # 25		1.00	85.00	5.50	0.30	140.25		
	4th Cross Amma Residency # 4		1.00	78.00	5.00	0.30	117.00		
	5th Cross #44 VR House		1.00	85.00	5.50	0.30	140.25		
	6th Cross Vaishnavi Beauty Care		1.00	60.00	5.50	0.30	99.00		
	3rd Main Road From End		1.00	540.00	6.00	0.30	972.00		
	Baba Nagar								
	2nd Main Road Near Hindustan Hardware		1.00	230.00	4.60	0.30	317.40		
	Shivapura Layout								
	Shiva parvathi Temple Road		1.00	220.00	5.00	0.30	330.00		
	Cross Road Sunrise Nest Appartment Beside Road		1.00	255.00	5.50	0.30	420.75		
	6th Cross Road		1.00	128.00	7.00	0.30	268.80		
	5th 'A' Cross Road		1.00	171.00	6.50	0.30	333.45		
	5th 'B' Cross Road		1.00	58.00	6.50	0.30	113.10		
	4th 'A' Cross Road		1.00	145.00	6.50	0.30	282.75		
	4th 'B' Cross Road		1.00	65.00	5.50	0.30	107.25		
	3rd 'A' Cross Road		1.00	47.00	4.50	0.30	63.45		
	3rd 'B' Cross Road		1.00	70.00	4.50	0.30	94.50		
	2nd 'A' Cross Road		1.00	48.00	5.00	0.30	72.00		
	2nd 'B' Cross Road		1.00	220.00	5.20	0.30	343.20		
	Cross Road		1.00	65.00	5.50	0.30	107.25		
	Chethan Nilaya # 41		1.00	62.00	6.00	0.30	111.60		
	1st 'A' Cross road		1.00	52.00	6.00	0.30	93.60		
	1st 'B' Cross Road		1.00	210.00	6.00	0.30	378.00		
	Srinivasa Hotel Road		1.00	64.00	6.00	0.30	115.20		
	Sunrise Nest Appartment Road		1.00	224.00	5.00	0.30	336.00		
	Muneshawara Layout								

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
t Main Road		1.00	96.00	5.50	0.30	158.40		
4th 'A' Cross road		1.00	65.00	6.00	0.30	117.00		
Kattigenahalli Govt School Road		1.00	54.00	6.70	0.30	108.54		
3rd Main Road From End		1.00	102.00	5.00	0.30	153.00		
3rd Cross Road From End		1.00	221.00	5.50	0.30	364.65		
2nd Cross Road		1.00	228.00	6.50	0.30	444.60		
2nd Main Road From 4th Cross		1.00	75.00	5.50	0.30	123.75		
1st Cross Road From end		1.00	220.00	4.50	0.30	297.00		
Main Road		1.00	188.00	5.00	0.30	282.00		
Saptagiri Layout								
Binod Electronics Road/ Arunpandit # 26 'A' 3rd B Cross		1.00	105.00	5.50	0.30	173.25		
Sri Angenaiya Nilaya # 16,17		1.00	81.00	6.00	0.30	145.80		
Sri Chowdeshwari Nilaya Front Road #36		1.00	68.00	5.50	0.30	112.20		
Sri Chowdeshwari Nilaya Right Road #36		1.00	65.00	6.00	0.30	117.00		
Sri Laxmi Venkateshawara Nilaya # 58		1.00	65.00	6.00	0.30	117.00		
1st Main Road		1.00	105.00	5.00	0.30	157.50		
Anantam Nilaya # 42 & 43		1.00	98.00	4.50	0.30	132.30		
Someshawara Layout								
Sri Siddeshawara General Store Road		1.00	75.00	6.80	0.30	153.00		
Sri Ramanginaiya Nilaya # 9		1.00	130.00	6.00	0.30	234.00		
Gangothri Badavani								
1st Cross Road		1.00	55.00	4.40	0.30	72.60		
2nd Cross Road		1.00	65.00	4.00	0.30	78.00		
3rd Cross Road		1.00	72.00	5.30	0.30	114.48		
Poojappa Layout								
4th Cross Road		1.00	350.00	5.00	0.30	525.00		
Cross Road		1.00	80.00	5.00	0.30	120.00		
Muneshawara Swamy General Store		1.00	100.00	5.00	0.30	150.00		
Kempegowda Layout								
Main Road		1.00	185.00	5.00	0.30	277.50		
1st Main Road		1.00	145.00	4.50	0.30	195.75		
Cross Road-5		1.00	65.00	4.50	0.30	87.75		
Cross Road-4 Bilal Imam #103/17		1.00	192.00	4.50	0.30	259.20		
Cross Road -3 Guru Krupa # 40		1.00	94.00	4.50	0.30	126.90		
Cross Road -2		1.00	56.00	4.50	0.30	75.60		
Cross Road-1		1.00	95.00	5.30	0.30	151.05		
Cross Road-3		1.00	60.00	5.00	0.30	90.00		
Kattigenahalli Main Road		1.00	860.00	6.70	0.30	1728.60		
Dutta town ship								
Main Road		1.00	186.00	6.70	0.30	373.86		
2nd Cross Road SreeKaram Nilaya		1.00	40.00	7.10	0.30	85.20		
Cross Road-1		1.00	160.00	5.50	0.30	264.00		
Cross Road-2		1.00	120.00	5.00	0.30	180.00		
Cross Road at End		1.00	270.00	4.80	0.30	388.80		
Kuvempu Nagar 4th B Cross		1.00	85.00	5.00	0.30	127.50		
Anjanadri Layout								
2nd Cross Road		1.00	97.00	5.00	0.30	145.50		
Road Connecting 1 & 2nd Cross Roads		1.00	30.00	5.00	0.30	45.00		
1st Cross Road		1.00	110.00	5.00	0.30	165.00		
Agrahara Main Road (Thirumenahalli Lake)		1.00	240.00	6.50	0.30	468.00		
Thirumenahalli (Ward No-05)								
1st Cross Road		1.00	101.00	6.50	0.30	196.95		
2nd Cross Road		1.00	155.00	6.00	0.30	279.00		
MVM Sumo Institution Road		1.00	45.00	6.50	0.30	87.75		
Balaji Layout								
Pristine Woods Apartments		1.00	165.00	6.80	0.30	336.60		

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	ain Road		1.00	295.00	6.00	0.30	531.00		
	1st Cross road Left side		1.00	86.00	5.50	0.30	141.90		
	2nd Cross road Left side		1.00	50.00	5.00	0.30	75.00		
	3rd Cross road Left side		1.00	61.00	5.50	0.30	100.65		
	2nd Cross Road Right side		1.00	62.00	4.00	0.30	74.40		
	1st Cross Road Right side		1.00	60.00	4.00	0.30	72.00		
	3rd Cross Road Right		1.00	60.00	4.00	0.30	72.00		
	Cross Road		1.00	31.00	4.50	0.30	41.85		
	4th Cross Right Side		1.00	48.00	5.00	0.30	72.00		
	Cross Road		1.00	100.00	5.00	0.30	150.00		
	Mathru Layout								
	Main road		1.00	240.00	4.50	0.30	324.00		
	1st Cross Road		1.00	52.00	4.50	0.30	70.20		
	2nd Cross Road		1.00	14.80	5.00	0.30	22.20		
	Basavalingappa Nagar								
	Main Road		1.00	318.00	5.00	0.30	477.00		
	2nd Cross Road		1.00	213.00	5.00	0.30	319.50		
	Cross Road-1		1.00	66.00	4.50	0.30	89.10		
	Cross Road-2		1.00	30.00	4.00	0.30	36.00		
	Cross Road-3		1.00	30.00	4.00	0:30	36.00		
							20944.11	**54.8531**	**1148849.36**
	Approved rate	**54.8531**					✓	✓	✓
12	KSRRB M400-17. Providing, Laying, Spreading and Compacting cushed stone aggregates of granite/ trap/basalt to wetmix macadam specifications including pre mixing the materials with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base /base coarse on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specification.								
	Vijay Nagar Layout	**Cum**							
	5th Main Road From Entrance		1.00	596.00	6.80	0.25	1013.20		
	4th Main Road From End		1.00	210.00	6.00	0.25	315.00		
	1st Cross Hasini Grand Appartment Road		1.00	136.00	5.50	0.25	187.00		
	2nd Cross M. Valarmathi Muniratnam #7		1.00	105.00	6.00	0.25	157.50		
	3rd Cross Sri Chowdeshawari Nilaya Laxmi Anjinappa # 25		1.00	85.00	5.50	0.25	116.88		
	4th Cross Amma Residency # 4		1.00	78.00	5.00	0.25	97.50		
	5th Cross #44 VR House		1.00	85.00	5.50	0.25	116.88		
	6th Cross Vaishnavi Beauty Care		1.00	60.00	5.50	0.25	82.50		
	3rd Main Road From End		1.00	540.00	6.00	0.25	810.00		
	Baba Nagar								
	2nd Main Road Near Hindustan Hardware		1.00	230.00	4.60	0.25	264.50		
	Shivapura Layout								
	Shiva parvathi Temple Road		1.00	220.00	5.00	0.25	275.00		
	Cross Road Sunrise Nest Appartment Beside Road		1.00	255.00	5.50	0.25	350.63		
	6th Cross Road		1.00	128.00	7.00	0.25	224.00		
	5th 'A' Cross Road		1.00	171.00	6.50	0.25	277.88		
	5th 'B' Cross Road		1.00	58.00	6.50	0.25	94.25		
	4th 'A' Cross Road		1.00	145.00	6.50	0.25	235.63		
	4th 'B' Cross Road		1.00	65.00	5.50	0.25	89.38		
	3rd 'A' Cross Road		1.00	47.00	4.50	0.25	52.88		
	3rd 'B' Cross Road		1.00	70.00	4.50	0.25	78.75		
	2nd 'A' Cross Road		1.00	48.00	5.00	0.25	60.00		
	2nd 'B' Cross Road		1.00	220.00	5.20	0.25	286.00		
	Cross Road		1.00	65.00	5.50	0.25	89.38		
	Chethan Nilaya # 41		1.00	62.00	6.00	0.25	93.00		
	1st 'A' Cross road		1.00	52.00	6.00	0.25	78.00		
	1st 'B' Cross Road		1.00	210.00	6.00	0.25	315.00		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
inivasa Hotel Road								
Sunrise Nest Appartment Road		1.00	64.00	6.00	0.25	96.00		
Muneshawara Layout		1.00	224.00	5.00	0.25	280.00		
1st Main Road								
4th 'A' Cross road		1.00	96.00	5.50	0.25	132.00		
Kattigenahalli Govt School Road		1.00	65.00	6.00	0.25	97.50		
3rd Main Road From End		1.00	54.00	6.70	0.25	90.45		
3rd Cross Road From End		1.00	102.00	5.00	0.25	127.50		
2nd Cross Road		1.00	221.00	5.50	0.25	303.88		
2nd Main Road From 4th Cross		1.00	228.00	6.50	0.25	370.50		
1st Cross Road From end		1.00	75.00	5.50	0.25	103.13		
Main Road		1.00	220.00	4.50	0.25	247.50		
Saptagiri Layout		1.00	188.00	5.00	0.25	235.00		
Binod Electronics Road/ Arunpandit # 26 'A' 3rd B Cross		1.00	105.00	5.50	0.25	144.38		
Sri Angenaiya Nilaya # 16.17		1.00	81.00	6.00	0.25	121.50		
Sri Chowdeshwari Nilaya Front Road #36		1.00	68.00	5.50	0.25	93.50		
Sri Chowdeshwari Nilaya Right Road #36		1.00	65.00	6.00	0.25	97.50		
Sri Laxmi Venkateshawara Nilaya # 58		1.00	65.00	6.00	0.25	97.50		
1st Main Road		1.00	105.00	5.00	0.25	131.25		
Anantam Nilaya # 42 & 43		1.00	98.00	4.50	0.25	110.25		
Someshawara Layout								
Sri Siddeshawara General Store Road		1.00	75.00	6.80	0.25	127.50		
Sri Ramanginaiya Nilaya # 9		1.00	130.00	6.00	0.25	195.00		
Gangothri Badavani								
1st Cross Road		1.00	55.00	4.40	0.25	60.50		
2nd Cross Road		1.00	65.00	4.00	0.25	65.00		
3rd Cross Road		1.00	72.00	5.30	0.25	95.40		
Poojappa Layout								
4th Cross Road		1.00	350.00	5.00	0.25	437.50		
Cross Road		1.00	80.00	5.00	0.25	100.00		
Muneshawara Swamy General Store		1.00	100.00	5.00	0.25	125.00		
Kempegowda Layout								
Main Road		1.00	185.00	5.00	0.25	231.25		
1st Main Road		1.00	145.00	4.50	0.25	163.13		
Cross Road-5		1.00	65.00	4.50	0.25	73.13		
Cross Road-4 Bilal Imam #103/17		1.00	192.00	4.50	0.25	216.00		
Cross Road -3 Guru Krupa # 40		1.00	94.00	4.50	0.25	105.75		
Cross Road -2		1.00	56.00	4.50	0.25	63.00		
Cross Road-1		1.00	95.00	5.30	0.25	125.88		
Cross Road-3		1.00	60.00	5.00	0.25	75.00		
Kattigenahalli Main Road		1.00	860.00	7.50	0.25	1612.50		
Dutta town ship								
Main Road		1.00	186.00	6.70	0.25	311.55		
2nd Cross Road SreeKaram Nilaya		1.00	40.00	7.10	0.25	71.00		
Cross Road-1		1.00	160.00	5.50	0.25	220.00		
Cross Road-2		1.00	120.00	5.00	0.25	150.00		
Cross Road at End		1.00	270.00	4.80	0.25	324.00		
Kuvempu Nagar 4th B Cross		1.00	85.00	5.00	0.25	106.25		
Anjanadri Layout								
2nd Cross Road		1.00	97.00	5.00	0.25	121.25		
Road Connecting 1 & 2nd Cross Roads		1.00	30.00	5.00	0.25	37.50		
1st Cross Road		1.00	110.00	5.00	0.25	137.50		
Agrahara Main Road (Thirumenahalli Lake)		1.00	240.00	6.50	0.25	390.00		
Thirumenahalli (Ward No-05)								
1st Cross Road		1.00	101.00	6.50	0.25	164.13		

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	d Cross Road		1.00	155.00	6.00	0.25	232.50		
	MVM Sumo Institution Road		1.00	45.00	6.50	0.25	73.13		
	Balaji Layout								
	Pristine Woods Apartments		1.00	165.00	6.80	0.25	280.50		
	Main Road		1.00	295.00	7.50	0.25	553.13		
	1st Cross road Left side		1.00	86.00	7.00	0.25	150.50		
	2nd Cross road Left side		1.00	50.00	6.00	0.25	75.00		
	3rd Cross road Left side		1.00	61.00	6.00	0.25	91.50		
	2nd Cross Road Right side		1.00	62.00	6.50	0.25	100.75		
	1st Cross Road Right side		1.00	60.00	6.50	0.25	97.50		
	3rd Cross Road Right		1.00	60.00	6.20	0.25	93.00		
	Cross Road		1.00	31.00	5.00	0.25	38.75		
	4th Cross Right Side		1.00	48.00	5.00	0.25	60.00		
	Cross Road		1.00	100.00	5.00	0.25	125.00		
	Mathru Layout								
	Main road		1.00	240.00	5.50	0.25	330.00		
	1st Cross Road		1.00	52.00	5.50	0.25	71.50		
	2nd Cross Road		1.00	14.80	5.50	0.25	20.35		
	Basavalingappa Nagar								
	Main Road		1.00	318.00	5.00	0.25	397.50		
	2nd Cross Road		1.00	213.00	5.00	0.25	266.25		
	Cross Road-1		1.00	66.00	5.00	0.25	82.50		
	Cross Road-2		1.00	30.00	5.50	0.25	41.25		
	Cross Road-3		1.00	30.00	5.00	0.25	37.50		
							17762.45	**2021.2928**	**35903112.30**
	Approved rate	**2021.2928**							
13	Providing and applying primer coat with S.S bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. clause 502 of MORTH V revision.								
		Sqm							
	Vijay Nagar Layout	**Cum**							
	5th Main Road From Entrance		1.00	596.00	6.80		4052.80		
	4th Main Road From End		1.00	210.00	6.00		1260.00		
	1st Cross Hasini Grand Appartment Road		1.00	136.00	5.50		748.00		
	2nd Cross M. Valarmathi Muniratnam #7		1.00	105.00	6.00		630.00		
	3rd Cross Sri Chowdeshawari Nilaya Laxmi Anjinappa # 25		1.00	85.00	5.50		467.50		
	4th Cross Amma Residency # 4		1.00	78.00	5.00		390.00		
	5th Cross #44 VR House		1.00	85.00	5.50		467.50		
	6th Cross Vaishnavi Beauty Care		1.00	60.00	5.50		330.00		
	3rd Main Road From End		1.00	540.00	6.00		3240.00		
	Baba Nagar								
	2nd Main Road Near Hindustan Hardware		1.00	230.00	4.60		1058.00		
	Shivapura Layout								
	Shiva parvathi Temple Road		1.00	220.00	5.00		1100.00		
	Cross Road Sunrise Nest Appartment Beside Road		1.00	255.00	5.50		1402.50		
	6th Cross Road		1.00	128.00	7.00		896.00		
	5th 'A' Cross Road		1.00	171.00	6.50		1111.50		
	5th 'B' Cross Road		1.00	58.00	6.50		377.00		
	4th 'A' Cross Road		1.00	145.00	6.50		942.50		
	4th 'B' Cross Road		1.00	65.00	5.50		357.50		
	3rd 'A' Cross Road		1.00	47.00	4.50		211.50		
	3rd 'B' Cross Road		1.00	70.00	4.50		315.00		
	2nd 'A' Cross Road		1.00	48.00	5.00		240.00		
	2nd 'B' Cross Road		1.00	220.00	5.20		1144.00		
	Cross Road		1.00	65.00	5.50		357.50		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
ethan Nilaya # 41		1.00	62.00	6.00		372.00		
1st 'A' Cross road		1.00	52.00	6.00		312.00		
1st 'B' Cross Road		1.00	210.00	6.00		1260.00		
Srinivasa Hotel Road		1.00	64.00	6.00		384.00		
Sunrise Nest Appartment Road		1.00	224.00	5.00		1120.00		
Muneshawara Layout								
1st Main Road		1.00	96.00	5.50		528.00		
4th 'A' Cross road		1.00	65.00	6.00		390.00		
Kattigenahalli Govt School Road		1.00	54.00	6.70		361.80		
3rd Main Road From End		1.00	102.00	5.00		510.00		
3rd Cross Road From End		1.00	221.00	5.50		1215.50		
2nd Cross Road		1.00	228.00	6.50		1482.00		
2nd Main Road From 4th Cross		1.00	75.00	5.50		412.50		
1st Cross Road From end		1.00	220.00	4.50		990.00		
Main Road		1.00	188.00	5.00		940.00		
Saptagiri Layout								
Binod Electronics Road/ Arunpandit # 26 'A' 3rd B Cross		1.00	105.00	5.50		577.50		
Sri Angenaiya Nilaya # 16,17		1.00	81.00	6.00		486.00		
Sri Chowdeshwari Nilaya Front Road #36		1.00	68.00	5.50		374.00		
Sri Chowdeshwari Nilaya Right Road #36		1.00	65.00	6.00		390.00		
Sri Laxmi Venkateshawara Nilaya # 58		1.00	65.00	6.00		390.00		
1st Main Road		1.00	105.00	5.00		525.00		
Anantam Nilaya # 42 & 43		1.00	98.00	4.50		441.00		
Someshawara Layout								
Sri Siddeshawara General Store Road		1.00	75.00	6.80		510.00		
Sri Ramanginaiya Nilaya # 9		1.00	130.00	6.00		780.00		
Gangothri Badavani								
1st Cross Road		1.00	55.00	4.40		242.00		
2nd Cross Road		1.00	65.00	4.00		260.00		
3rd Cross Road		1.00	72.00	5.30		381.60		
Poojappa Layout								
4th Cross Road		1.00	350.00	5.00		1750.00		
Cross Road		1.00	80.00	5.00		400.00		
Muneshawara Swamy General Store		1.00	100.00	5.00		500.00		
Kempegowda Layout								
Main Road		1.00	185.00	5.00		925.00		
1st Main Road		1.00	145.00	4.50		652.50		
Cross Road-5		1.00	65.00	4.50		292.50		
Cross Road-4 Bilal Imam #103/17		1.00	192.00	4.50		864.00		
Cross Road -3 Guru Krupa # 40		1.00	94.00	4.50		423.00		
Cross Road -2		1.00	56.00	4.50		252.00		
Cross Road-1		1.00	95.00	5.30		503.50		
Cross Road-3		1.00	60.00	5.00		300.00		
Kattigenahalli Main Road		1.00	860.00	8.00		6880.00		
Dutta town ship								
Main Road		1.00	186.00	6.70		1246.20		
2nd Cross Road SreeKaram Nilaya		1.00	40.00	7.10		284.00		
Cross Road-1		1.00	160.00	5.50		880.00		
Cross Road-2		1.00	120.00	5.00		600.00		
Cross Road at End		1.00	270.00	4.80		1296.00		
Kuvempu Nagar 4th B Cross		1.00	85.00	5.00		425.00		
Anjanadri Layout								
2nd Cross Road		1.00	97.00	5.00		485.00		
Road Connecting 1 & 2nd Cross Roads		1.00	30.00	5.00		150.00		
1st Cross Road		1.00	110.00	5.00		550.00		

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Agrahara Main Road (Thirumenahalli Lake)		1.00	240.00	6.50		1560.00		
	Thirumenahalli (Ward No-05)								
	1st Cross Road		1.00	101.00	6.50		656.50		
	2nd Cross Road		1.00	155.00	6.00		930.00		
	MVM Sumo Institution Road		1.00	45.00	6.50		292.50		
	Balaji Layout								
	Pristine Woods Apartments		1.00	165.00	6.80		1122.00		
	Main Road		1.00	295.00	7.50		2212.50		
	1st Cross road Left side		1.00	86.00	6.00		516.00		
	2nd Cross road Left side		1.00	50.00	5.00		250.00		
	3rd Cross road Left side		1.00	61.00	5.50		335.50		
	2nd Cross Road Right side		1.00	62.00	6.50		403.00		
	1st Cross Road Right side		1.00	60.00	6.50		390.00		
	3rd Cross Road Right		1.00	60.00	5.00		300.00		
	Cross Road		1.00	31.00	5.00		155.00		
	4th Cross Right Side		1.00	48.00	5.00		240.00		
	Cross Road		1.00	100.00	5.00		500.00		
	Mathru Layout								
	Main road		1.00	240.00	5.50		1320.00		
	1st Cross Road		1.00	52.00	5.50		286.00		
	2nd Cross Road		1.00	14.80	5.50		81.40		
	Basavalingappa Nagar								
	Main Road		1.00	318.00	5.00		1590.00		
	2nd Cross Road		1.00	213.00	5.00		1065.00		
	Cross Road-1		1.00	66.00	5.00		330.00		
	Cross Road-2		1.00	30.00	5.50		165.00		
	Cross Road-3		1.00	30.00	5.00		150.00		
							72594.02	**28.9062**	**2098417.26**
	Approved rate	**28.9062**							
14	Cleaning the existing black topped surface with Sqm brooms soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM complete as per specifications.clause 502 of MORTH V revision.								
		Sqm							
	Shivapura Layout								
	Shiva parvathi Temple Road		1.00	220.00	5.00		1100.00		
	Cross Road Sunrise Nest Appartment Beside Road		1.00	255.00	5.50		1402.50		
	6th Cross Road		1.00	128.00	7.00		896.00		
	5th 'A' Cross Road		1.00	171.00	6.50		1111.50		
	5th 'B' Cross Road		1.00	58.00	6.50		377.00		
	4th 'A' Cross Road		1.00	145.00	6.50		942.50		
	4th 'B' Cross Road		1.00	65.00	5.50		357.50		
	3rd 'A' Cross Road		1.00	47.00	4.50		211.50		
	3rd 'B' Cross Road		1.00	70.00	4.50		315.00		
	2nd 'A' Cross Road		1.00	48.00	5.00		240.00		
	2nd 'B' Cross Road		1.00	220.00	5.20		1144.00		
	Cross Road		1.00	65.00	5.50		357.50		
	Chethan Nilaya # 41		1.00	62.00	6.00		372.00		
	1st 'A' Cross road		1.00	52.00	6.00		312.00		
	1st 'B' Cross Road		1.00	210.00	6.00		1260.00		
	Srinivasa Hotel Road		1.00	64.00	6.00		384.00		
	Sunrise Nest Appartment Road		1.00	224.00	5.00		1120.00		
	Saptagiri Layout								
	Binod Electronics Road/ Arunpandit # 26 'A' 3rd B Cross		1.00	105.00	5.50		577.50		
	Sri Angenaiya Nilaya # 16,17		1.00	81.00	6.00		486.00		
	Sri Chowdeshwari Nilaya Front Road #36		1.00	68.00	5.50		374.00		

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Sri Chowdeshwari Nilaya Right Road #36		1.00	65.00	6.00		390.00		
	Sri Laxmi Venkateshawara Nilaya # 58		1.00	65.00	6.00		390.00		
	1st Main Road		1.00	105.00	5.00		525.00		
	Anantam Nilaya # 42 & 43		1.00	98.00	4.50		441.00		
	Main Road		1.00	185.00	5.00		925.00		
	1st Main Road		1.00	145.00	4.50		652.50		
	Cross Road-5		1.00	65.00	4.50		292.50		
	Cross Road-4 Bilal Imam #103/17		1.00	192.00	4.50		864.00		
	Cross Road -3 Guru Krupa # 40		1.00	94.00	4.50		423.00		
	Cross Road -2		1.00	56.00	4.50		252.00		
	Cross Road-1		1.00	95.00	5.30		503.50		
	Cross Road-3		1.00	60.00	5.00		300.00		
	Dutta town ship								
	Main Road		1.00	186.00	6.70		1246.20		
	2nd Cross Road SreeKaram Nilaya		1.00	40.00	7.10		284.00		
	Cross Road-1		1.00	160.00	5.50		880.00		
	Cross Road-2		1.00	120.00	5.00		600.00		
	Cross Road at End		1.00	270.00	4.80		1296.00		
	Kuvempu Nagar 4th B Cross		1.00	85.00	5.00		425.00		
	Agrahara Main Road (Thirumenahalli Lake)		1.00	240.00	6.50		1560.00		
	Thirumenahalli (Ward No-05)								
	1st Cross Road		1.00	101.00	6.50		656.50		
	2nd Cross Road		1.00	155.00	6.00		930.00		
	MVM Sumo Institution Road		1.00	45.00	6.50		292.50		
	Balaji Layout								
	Pristine Woods Apartments		1.00	165.00	6.80		1122.00		
	Main Road		1.00	295.00	7.00		2065.00		
	1st Cross road Left side		1.00	86.00	6.00		516.00		
	2nd Cross road Left side		1.00	50.00	5.00		250.00		
	3rd Cross road Left side		1.00	61.00	5.50		335.50		
	2nd Cross Road Right side		1.00	62.00	6.50		403.00		
	1st Cross Road Right side		1.00	60.00	6.50		390.00		
	3rd Cross Road Right		1.00	60.00	5.00		300.00		
	Cross Road		1.00	31.00	5.00		155.00		
	4th Cross Right Side		1.00	48.00	5.00		240.00		
	Cross Road		1.00	100.00	5.00		500.00		
	Mathru Layout								
	Main road		1.00	240.00	5.35		1284.00		
	1st Cross Road		1.00	52.00	5.50		286.00		
	2nd Cross Road		1.00	14.80	5.50		81.40		
	Basavalingappa Nagar								
	Main Road		1.00	318.00	5.00		1590.00		
	2nd Cross Road		1.00	213.00	5.00		1065.00		
	Cross Road-1		1.00	66.00	5.00		330.00		
	Cross Road-2		1.00	30.00	5.50		165.00		
	Cross Road-3		1.00	30.00	5.00		150.00		
							38695.72	**5.3530**	**207138.19**
	Approved rate	**5.3530**					✓	✓	✓
15	Providing and applying tack coat using 80/100 grade Sqm bitumen(VGIO) in boiler fitted with spray set distributor at the rate of 0.25 kg per Sqm on the existing prepared bituminous surface cleaned with mechanical broom, complete as per specifications. clause 503 of MORTH V revision.								
	For DBM	Sqm							
	Shivapura Layout								
	Shiva parvathi Temple Road		1.00	220.00	5.00		1100.00		
	Cross Road Sunrise Nest Appartment Beside Road		1.00	255.00	5.50		1402.50		
	6th Cross Road		1.00	128.00	7.00		896.00		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
ih 'A' Cross Road		1.00	171.00	6.50		1111.50		
5th 'B' Cross Road		1.00	58.00	6.50		377.00		
4th 'A' Cross Road		1.00	145.00	6.50		942.50		
4th 'B' Cross Road		1.00	65.00	5.50		357.50		
3rd 'A' Cross Road		1.00	47.00	4.50		211.50		
3rd 'B' Cross Road		1.00	70.00	4.50		315.00		
2nd 'A' Cross Road		1.00	48.00	5.00		240.00		
2nd 'B' Cross Road		1.00	220.00	5.20		1144.00		
Cross Road		1.00	65.00	5.50		357.50		
Chethan Nilaya # 41		1.00	62.00	6.00		372.00		
1st 'A' Cross road		1.00	52.00	6.00		312.00		
1st 'B' Cross Road		1.00	210.00	6.00		1260.00		
Srinivasa Hotel Road		1.00	64.00	6.00		384.00		
Sunrise Nest Appartment Road		1.00	224.00	5.00		1120.00		
Saptagiri Layout								
Binod Electronics Road/ Arunpandit # 26 'A' 3rd B Cross		1.00	105.00	5.50		577.50		
Sri Angenaiya Nilaya # 16,17		1.00	81.00	6.00		486.00		
Sri Chowdeshwari Nilaya Front Road #36		1.00	68.00	5.50		374.00		
Sri Chowdeshwari Nilaya Right Road #36		1.00	65.00	6.00		390.00		
Sri Laxmi Venkateshawara Nilaya # 58		1.00	65.00	6.00		390.00		
1st Main Road		1.00	105.00	5.00		525.00		
Anantam Nilaya # 42 & 43		1.00	98.00	4.50		441.00		
Kempegowda Layout								
Main Road		1.00	185.00	5.00		925.00		
1st Main Road		1.00	145.00	4.50		652.50		
Cross Road-5		1.00	65.00	4.50		292.50		
Cross Road-4 Bilal Imam #103/17		1.00	192.00	4.50		864.00		
Cross Road -3 Guru Krupa # 40		1.00	94.00	4.50		423.00		
Cross Road -2		1.00	56.00	4.50		252.00		
Cross Road-1		1.00	95.00	5.30		503.50		
Kattigenahalli Main Road		1.00	860.00	7.50		6450.00		
Dutta town ship								
Main Road		1.00	186.00	6.70		1246.20		
2nd Cross Road SreeKaram Nilaya		1.00	40.00	7.10		284.00		
Cross Road-1		1.00	160.00	5.50		880.00		
Cross Road-2		1.00	120.00	5.00		600.00		
Cross Road at End		1.00	270.00	4.80		1296.00		
Kuvempu Nagar 4th B Cross		1.00	85.00	5.00		425.00		
Anjanadri Layout								
2nd Cross Road		1.00	97.00	5.00		485.00		
Road Connecting 1 & 2nd Cross Roads		1.00	30.00	5.00		150.00		
1st Cross Road		1.00	110.00	5.00		550.00		
Agrahara Main Road (Thirumenahalli Lake)		1.00	240.00	6.50		1560.00		
Thirumenahalli (Ward No-05)								
1st Cross Road		1.00	101.00	6.50		656.50		
2nd Cross Road		1.00	155.00	6.00		930.00		
MVM Sumo Institution Road		1.00	45.00	6.50		292.50		
Balaji Layout								
Pristine Woods Apartments		1.00	165.00	6.80		1122.00		
Main Road		1.00	295.00	7.50		2212.50		
1st Cross road Left side		1.00	86.00	6.00		516.00		
2nd Cross road Left side		1.00	50.00	5.00		250.00		
3rd Cross road Left side		1.00	61.00	5.50		335.50		
2nd Cross Road Right side		1.00	62.00	6.50		403.00		
1st Cross Road Right side		1.00	60.00	6.50		390.00		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
rd Cross Road Right		1.00	60.00	5.00		300.00		
Cross Road		1.00	31.00	5.00		155.00		
4th Cross Right Side		1.00	48.00	5.00		240.00		
Cross Road		1.00	100.00	5.00		500.00		
For BC								
Vijay Nagar Layout								
5th Main Road From Entrance		1.00	596.00	6.80		4052.80		
4th Main Road From End		1.00	210.00	6.00		1260.00		
1st Cross Hasini Grand Appartment Road		1.00	136.00	5.50		748.00		
2nd Cross M. Valarmathi Muniratnam #7		1.00	105.00	6.00		630.00		
3rd Cross Sri Chowdeshawari Nilaya Laxmi Anjinappa # 25		1.00	85.00	5.50		467.50		
4th Cross Amma Residency # 4		1.00	78.00	5.00		390.00		
5th Cross #44 VR House		1.00	85.00	5.50		467.50		
6th Cross Vaishnavi Beauty Care		1.00	60.00	5.50		330.00		
3rd Main Road From End		1.00	540.00	6.00		3240.00		
Baba Nagar								
2nd Main Road Near Hindustan Hardware		1.00	230.00	4.60		1058.00		
Shivapura Layout								
Shiva parvathi Temple Road		1.00	220.00	5.00		1100.00		
Cross Road Sunrise Nest Appartment Beside Road		1.00	255.00	5.50		1402.50		
6th Cross Road		1.00	128.00	7.00		896.00		
5th 'A' Cross Road		1.00	171.00	6.50		1111.50		
5th 'B' Cross Road		1.00	58.00	6.50		377.00		
4th 'A' Cross Road		1.00	145.00	6.50		942.50		
4th 'B' Cross Road		1.00	65.00	5.50		357.50		
3rd 'A' Cross Road		1.00	47.00	4.50		211.50		
3rd 'B' Cross Road		1.00	70.00	4.50		315.00		
2nd 'A' Cross Road		1.00	48.00	5.00		240.00		
2nd 'B' Cross Road		1.00	220.00	5.20		1144.00		
Cross Road		1.00	65.00	5.50		357.50		
Chethan Nilaya # 41		1.00	62.00	6.00		372.00		
1st 'A' Cross road		1.00	52.00	6.00		312.00		
1st 'B' Cross Road		1.00	210.00	6.00		1260.00		
Srinivasa Hotel Road		1.00	64.00	6.00		384.00		
Sunrise Nest Appartment Road		1.00	224.00	5.00		1120.00		
Muneshawara Layout								
1st Main Road		1.00	96.00	5.50		528.00		
4th 'A' Cross road		1.00	65.00	6.00		390.00		
Kattigenahalli Govt School Road		1.00	54.00	6.70		361.80		
3rd Main Road From End		1.00	102.00	5.00		510.00		
3rd Cross Road From End		1.00	221.00	5.50		1215.50		
2nd Cross Road		1.00	228.00	6.50		1482.00		
2nd Main Road From 4th Cross		1.00	75.00	5.50		412.50		
1st Cross Road From end		1.00	220.00	4.50		990.00		
Main Road		1.00	188.00	5.00		940.00		
Saptagiri Layout								
Binod Electronics Road/ Arunpandit # 26 'A' 3rd B Cross		1.00	105.00	5.50		577.50		
Sri Angenaiya Nilaya # 16,17		1.00	81.00	6.00		486.00		
Sri Chowdeshwari Nilaya Front Road #36		1.00	68.00	5.50		374.00		
Sri Chowdeshwari Nilaya Right Road #36		1.00	65.00	6.00		390.00		
Sri Laxmi Venkateshawara Nilaya # 58		1.00	65.00	6.00		390.00		
1st Main Road		1.00	105.00	5.00		525.00		
Anantam Nilaya # 42 & 43		1.00	98.00	4.50		441.00		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
meshawara Layout								
Sri Siddeshawara General Store Road		1.00	75.00	6.80		510.00		
Sri Ramanginaiya Nilaya # 9		1.00	130.00	6.00		780.00		
Gangothri Badavani								
1st Cross Road		1.00	55.00	4.40		242.00		
2nd Cross Road		1.00	65.00	4.00		260.00		
3rd Cross Road		1.00	72.00	5.30		381.60		
Poojappa Layout								
4th Cross Road		1.00	350.00	5.00		1750.00		
Cross Road		1.00	80.00	5.00		400.00		
Muneshawara Swamy General Store		1.00	100.00	5.00		500.00		
Kempegowda Layout								
Main Road		1.00	185.00	5.00		925.00		
1st Main Road		1.00	145.00	4.50		652.50		
Cross Road-5		1.00	65.00	4.50		292.50		
Cross Road-4 Bilal Imam #103/17		1.00	192.00	4.50		864.00		
Cross Road -3 Guru Krupa # 40		1.00	94.00	4.50		423.00		
Cross Road -2		1.00	56.00	4.50		252.00		
Cross Road-1		1.00	95.00	5.30		503.50		
Kattigenahalli Main Road		1.00	860.00	7.50		6450.00		
Dutta town ship								
Main Road		1.00	186.00	6.70		1246.20		
2nd Cross Road SreeKaram Nilaya		1.00	40.00	7.10		284.00		
Cross Road-1		1.00	160.00	5.50		880.00		
Cross Road-2		1.00	120.00	5.00		600.00		
Cross Road at End		1.00	270.00	4.80		1296.00		
Kuvempu Nagar 4th B Cross		1.00	85.00	5.00		425.00		
Anjanadri Layout								
2nd Cross Road		1.00	97.00	5.00		485.00		
Road Connecting 1 & 2nd Cross Roads		1.00	30.00	5.00		150.00		
1st Cross Road		1.00	110.00	5.00		550.00		
Agrahara Main Road (Thirumenahalli Lake)		1.00	240.00	6.50		1560.00		
Thirumenahalli (Ward No-05)								
1st Cross Road		1.00	101.00	6.50		656.50		
2nd Cross Road		1.00	155.00	6.00		930.00		
MVM Sumo Institution Road		1.00	45.00	6.50		292.50		
Balaji Layout								
Pristine Woods Apartments		1.00	165.00	6.80		1122.00		
Main Road		1.00	295.00	7.50		2212.50		
1st Cross road Left side		1.00	86.00	6.00		516.00		
2nd Cross road Left side		1.00	50.00	5.00		250.00		
3rd Cross road Left side		1.00	61.00	5.50		335.50		
2nd Cross Road Right side		1.00	62.00	6.50		403.00		
1st Cross Road Right side		1.00	60.00	6.50		390.00		
3rd Cross Road Right		1.00	60.00	5.00		300.00		
Cross Road		1.00	31.00	5.00		155.00		
4th Cross Right Side		1.00	48.00	5.00		240.00		
Cross Road		1.00	100.00	5.00		500.00		
Mathru Layout								
Main road		1.00	240.00	5.35		1284.00		
1st Cross Road		1.00	52.00	5.50		286.00		
2nd Cross Road		1.00	14.80	5.50		81.40		
Basavalingappa Nagar								
Main Road		1.00	318.00	5.00		1590.00		
2nd Cross Road		1.00	213.00	5.00		1065.00		
Cross Road-1		1.00	66.00	5.00		330.00		
Cross Road-2		1.00	30.00	5.50		165.00		
Cross Road-3		1.00	30.00	5.00		150.00		

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Approved rate	**12.8472**					**112740.25**	**12.8472**	**1448396.54**
16	Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, lavel and allignment, rolling with smooth wheeled, vibratory and tandom rollers to achieve the desired compaction as per MORTH table 500-10 Complete in all respects compete as per specifications MORTH specification No. 507. using 100/120 TPH capacity HMP with sensor paver Gr-II (50mm to 75mm) with 4.5 % VG-30 Bitumen.								
	Vijay Nagar Layout	**Cum**							
	5th Main Road From Entrance		1.00	596.00	6.80	0.05	202.64		
	4th Main Road From End		1.00	210.00	6.00	0.05	63.00		
	1st Cross Hasini Grand Appartment Road		1.00	136.00	5.50	0.05	37.40		
	2nd Cross M. Valarmathi Muniratnam #7		1.00	105.00	6.00	0.05	31.50		
	3rd Cross Sri Chowdeshawari Nilaya Laxmi Anjinappa # 25		1.00	85.00	5.50	0.05	23.38		
	4th Cross Amma Residency # 4		1.00	78.00	5.00	0.05	19.50		
	5th Cross #44 VR House		1.00	85.00	5.50	0.05	23.38		
	6th Cross Vaishnavi Beauty Care		1.00	60.00	5.50	0.05	16.50		
	3rd Main Road From End		1.00	540.00	6.00	0.05	162.00		
	Shivapura Layout								
	Shiva parvathi Temple Road		1.00	220.00	5.00	0.05	55.00		
	Cross Road Sunrise Nest Appartment Beside Road		1.00	255.00	5.50	0.05	70.13		
	6th Cross Road		1.00	128.00	7.00	0.05	44.80		
	5th 'A' Cross Road		1.00	171.00	6.50	0.05	55.58		
	5th 'B' Cross Road		1.00	58.00	6.50	0.05	18.85		
	4th 'A' Cross Road		1.00	145.00	6.50	0.05	47.13		
	4th 'B' Cross Road		1.00	65.00	5.50	0.05	17.88		
	3rd 'A' Cross Road		1.00	47.00	4.50	0.05	10.58		
	3rd 'B' Cross Road		1.00	70.00	4.50	0.05	15.75		
	2nd 'A' Cross Road		1.00	48.00	5.00	0.05	12.00		
	2nd 'B' Cross Road		1.00	220.00	5.20	0.05	57.20		
	Cross Road		1.00	65.00	5.50	0.05	17.88		
	Chethan Nilaya # 41		1.00	62.00	6.00	0.05	18.60		
	1st 'A' Cross road		1.00	52.00	6.00	0.05	15.60		
	1st 'B' Cross Road		1.00	210.00	6.00	0.05	63.00		
	Srinivasa Hotel Road		1.00	64.00	6.00	0.05	19.20		
	Sunrise Nest Appartment Road		1.00	224.00	5.00	0.05	56.00		
	Muneshawara Layout								
	1st Main Road		1.00	96.00	5.50	0.05	26.40		
	4th 'A' Cross road		1.00	65.00	6.00	0.05	19.50		
	Kattigenahalli Govt School Road		1.00	54.00	6.70	0.05	18.09		
	3rd Main Road From End		1.00	102.00	5.00	0.05	25.50		
	3rd Cross Road From End		1.00	221.00	5.50	0.05	60.78		
	2nd Cross Road		1.00	228.00	6.50	0.05	74.10		
	2nd Main Road From 4th Cross		1.00	75.00	5.50	0.05	20.63		
	1st Cross Road From end		1.00	220.00	4.50	0.05	49.50		
	Main Road		1.00	188.00	5.00	0.05	47.00		
	Saptagiri Layout								
	Binod Electronics Road/ Arunpandit # 26 'A' 3rd B Cross		1.00	105.00	5.50	0.05	28.88		
	Sri Angenaiya Nilaya # 16,17		1.00	81.00	6.00	0.05	24.30		
	Sri Chowdeshwari Nilaya Front Road #36		1.00	68.00	5.50	0.05	18.70		
	Sri Chowdeshwari Nilaya Right Road #36		1.00	65.00	6.00	0.05	19.50		
	Sri Laxmi Venkateshawara Nilaya # 58		1.00	65.00	6.00	0.05	19.50		
	1st Main Road		1.00	105.00	5.00	0.05	26.25		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
...antam Nilaya # 42 & 43		1.00	98.00	4.50	0.05	22.05		
Someshawara Layout								
Sri Siddeshawara General Store Road		1.00	75.00	6.80	0.05	25.50		
Sri Ramanginaiya Nilaya # 9		1.00	130.00	6.00	0.05	39.00		
Gangothri Badavani								
1st Cross Road		1.00	55.00	4.40	0.05	12.10		
2nd Cross Road		1.00	65.00	4.00	0.05	13.00		
3rd Cross Road		1.00	72.00	5.30	0.05	19.08		
Poojappa Layout								
4th Cross Road		1.00	350.00	5.00	0.05	87.50		
Cross Road		1.00	80.00	5.00	0.05	20.00		
Muneshawara Swamy General Store		1.00	100.00	5.00	0.05	25.00		
Kempegowda Layout								
Main Road		1.00	185.00	5.00	0.05	46.25		
1st Main Road		1.00	145.00	4.50	0.05	32.63		
Cross Road-5		1.00	65.00	4.50	0.05	14.63		
Cross Road-4 Bilal Imam #103/17		1.00	192.00	4.50	0.05	43.20		
Cross Road -3 Guru Krupa # 40		1.00	94.00	4.50	0.05	21.15		
Cross Road -2		1.00	56.00	4.50	0.05	12.60		
Cross Road-1		1.00	95.00	5.30	0.05	25.18		
Kattigenahalli Main Road		1.00	860.00	7.50	0.05	322.50		
Dutta town ship								
Main Road		1.00	186.00	6.70	0.05	62.31		
2nd Cross Road SreeKaram Nilaya		1.00	40.00	7.10	0.05	14.20		
Cross Road-1		1.00	160.00	5.50	0.05	44.00		
Cross Road-2		1.00	120.00	5.00	0.05	30.00		
Cross Road at End		1.00	270.00	4.80	0.05	64.80		
Kuvempu Nagar 4th B Cross		1.00	85.00	5.00	0.05	21.25		
Anjanadri Layout								
2nd Cross Road		1.00	97.00	5.00	0.05	24.25		
Road Connecting 1 & 2nd Cross Roads		1.00	30.00	5.00	0.05	7.50		
1st Cross Road		1.00	110.00	5.00	0.05	27.50		
Agrahara Main Road (Thirumenahalli Lake)		1.00	240.00	6.50	0.05	78.00		
Thirumenahalli (Ward No-05)								
1st Cross Road		1.00	101.00	6.50	0.05	32.83		
2nd Cross Road		1.00	155.00	6.00	0.05	46.50		
MVM Sumo Institution Road		1.00	45.00	6.50	0.05	14.63		
Balaji Layout								
Pristine Woods Apartments		1.00	165.00	6.80	0.05	56.10		
Main Road		1.00	295.00	7.50	0.05	110.63		
1st Cross road Left side		1.00	86.00	6.00	0.05	25.80		
2nd Cross Road Right side		1.00	62.00	6.50	0.05	20.15		
1st Cross Road Right side		1.00	60.00	6.50	0.05	19.50		
3rd Cross Road Right		1.00	60.00	5.00	0.05	15.00		
Cross Road		1.00	31.00	5.00	0.05	7.75		
4th Cross Right Side		1.00	48.00	5.00	0.05	12.00		
Cross Road		1.00	100.00	5.00	0.05	25.00		
Mathru Layout								
Main road		1.00	240.00	5.35	0.05	64.20		
1st Cross Road		1.00	52.00	5.50	0.05	14.30		
Basavalingappa Nagar								
Main Road		1.00	318.00	5.00	0.05	79.50		
2nd Cross Road		1.00	213.00	5.00	0.05	53.25		
						3401.10	**6663.4144**	**22662938.72**
Approved rate	**6663.4144**					✓	✓	✓

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
17	oviding and laying bituminous concrete 40mm thick with hot mix plant, using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4% of modified bituminous binder consisting of 4.97% of VG-30 bitumen(60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic) crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site laying with a paver finisher to required grade level and allignment rooling with smooth wheeled vibratory and tandem rollers to achive the desired compaction in all respects complete as per specifications								
		Cum							
	Vijay Nagar Layout	Cum							
	5th Main Road From Entrance		1.00	596.00	6.80	0.04	162.11		
	4th Main Road From End		1.00	210.00	6.00	0.04	50.40		
	1st Cross Hasini Grand Appartment Road		1.00	136.00	5.50	0.04	29.92		
	2nd Cross M. Valarmathi Muniratnam #7		1.00	105.00	6.00	0.04	25.20		
	3rd Cross Sri Chowdeshawari Nilaya Laxmi Anjinappa # 25		1.00	85.00	5.50	0.04	18.70		
	4th Cross Amma Residency # 4		1.00	78.00	5.00	0.04	15.60		
	5th Cross #44 VR House		1.00	85.00	5.50	0.04	18.70		
	6th Cross Vaishnavi Beauty Care		1.00	60.00	5.50	0.04	13.20		
	3rd Main Road From End		1.00	540.00	6.00	0.04	129.60		
	Baba Nagar								
	2nd Main Road Near Hindustan Hardware		1.00	230.00	4.60	0.04	42.32		
	Shivapura Layout					0.04			
	Shiva parvathi Temple Road		1.00	220.00	5.00	0.04	44.00		
	Cross Road Sunrise Nest Appartment Beside Road		1.00	255.00	5.50	0.04	56.10		
	6th Cross Road		1.00	128.00	7.00	0.04	35.84		
	5th 'A' Cross Road		1.00	171.00	6.50	0.04	44.46		
	5th 'B' Cross Road		1.00	58.00	6.50	0.04	15.08		
	4th 'A' Cross Road		1.00	145.00	6.50	0.04	37.70		
	4th 'B' Cross Road		1.00	65.00	5.50	0.04	14.30		
	3rd 'A' Cross Road		1.00	47.00	4.50	0.04	8.46		
	3rd 'B' Cross Road		1.00	70.00	4.50	0.04	12.60		
	2nd 'A' Cross Road		1.00	48.00	5.00	0.04	9.60		
	2nd 'B' Cross Road		1.00	220.00	5.20	0.04	45.76		
	Cross Road		1.00	65.00	5.50	0.04	14.30		
	Chethan Nilaya # 41		1.00	62.00	6.00	0.04	14.88		
	1st 'A' Cross road		1.00	52.00	6.00	0.04	12.48		
	1st 'B' Cross Road		1.00	210.00	6.00	0.04	50.40		
	Srinivasa Hotel Road		1.00	64.00	6.00	0.04	15.36		
	Sunrise Nest Appartment Road		1.00	224.00	5.00	0.04	44.80		
	Muneshawara Layout								
	1st Main Road		1.00	96.00	5.50	0.04	21.12		
	4th 'A' Cross road		1.00	65.00	6.00	0.04	15.60		
	Kattigenahalli Govt School Road		1.00	54.00	6.70	0.04	14.47		
	3rd Main Road From End		1.00	102.00	5.00	0.04	20.40		
	3rd Cross Road From End		1.00	221.00	5.50	0.04	48.62		
	2nd Cross Road		1.00	228.00	6.50	0.04	59.28		
	2nd Main Road From 4th Cross		1.00	75.00	5.50	0.04	16.50		
	1st Cross Road From end		1.00	220.00	6.50	0.04	57.20		
	Main Road		1.00	188.00	5.00	0.04	37.60		
	Saptagiri Layout								
	Binod Electronics Road/ Arunpandit # 26 'A' 3rd B Cross		1.00	105.00	5.50	0.04	23.10		
	Sri Angenaiya Nilaya # 16,17		1.00	81.00	6.00	0.04	19.44		
	Sri Chowdeshwari Nilaya Front Road #36		1.00	68.00	5.50	0.04	14.96		
	Sri Chowdeshwari Nilaya Right Road #36		1.00	65.00	6.00	0.04	15.60		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Sri Laxmi Venkateshawara Nilaya # 58		1.00	65.00	6.00	0.04	15.60		
1st Main Road		1.00	105.00	5.00	0.04	21.00		
Anantam Nilaya # 42 & 43		1.00	98.00	4.50	0.04	17.64		
Someshawara Layout								
Sri Siddeshawara General Store Road		1.00	75.00	6.80	0.04	20.40		
Sri Ramanginaiya Nilaya # 9		1.00	130.00	6.00	0.04	31.20		
Gangothri Badavani								
1st Cross Road		1.00	55.00	4.40	0.04	9.68		
2nd Cross Road		1.00	65.00	4.00	0.04	10.40		
3rd Cross Road		1.00	72.00	5.30	0.04	15.26		
Poojappa Layout								
4th Cross Road		1.00	350.00	5.00	0.04	70.00		
Cross Road		1.00	80.00	5.00	0.04	16.00		
Muneshawara Swamy General Store		1.00	100.00	5.00	0.04	20.00		
Kempegowda Layout								
Main Road		1.00	185.00	5.00	0.04	37.00		
1st Main Road		1.00	145.00	4.50	0.04	26.10		
Cross Road-5		1.00	65.00	4.50	0.04	11.70		
Cross Road-4 Bilal Imam #103/17		1.00	192.00	4.50	0.04	34.56		
Cross Road -3 Guru Krupa # 40		1.00	94.00	4.50	0.04	16.92		
Cross Road -2		1.00	56.00	4.50	0.04	10.08		
Cross Road-1		1.00	95.00	5.30	0.04	20.14		
Cross Road-3		1.00	60.00	5.00	0.04	12.00		
Kattigenahalli Main Road		1.00	860.00	8.50	0.04	292.40		
Dutta town ship								
Main Road		1.00	186.00	6.70	0.04	49.85		
2nd Cross Road SreeKaram Nilaya		1.00	40.00	7.10	0.04	11.36		
Cross Road-1		1.00	160.00	5.50	0.04	35.20		
Cross Road-2		1.00	120.00	5.00	0.04	24.00		
Cross Road at End		1.00	270.00	4.80	0.04	51.84		
Kuvempu Nagar 4th B Cross		1.00	85.00	5.00	0.04	17.00		
Anjanadri Layout								
2nd Cross Road		1.00	97.00	5.00	0.04	19.40		
Road Connecting 1 & 2nd Cross Roads		1.00	30.00	5.00	0.04	6.00		
1st Cross Road		1.00	110.00	5.00	0.04	22.00		
Agrahara Main Road (Thirumenahalli Lake)		1.00	240.00	6.50	0.04	62.40		
Thirumenahalli (Ward No-05)								
1st Cross Road		1.00	101.00	6.50	0.04	26.26		
2nd Cross Road		1.00	155.00	6.00	0.04	37.20		
MVM Sumo Institution Road		1.00	45.00	6.50	0.04	11.70		
Balaji Layout								
Pristine Woods Apartments		1.00	165.00	7.50	0.04	49.50		
Main Road		1.00	295.00	7.50	0.04	88.50		
1st Cross road Left side		1.00	86.00	6.00	0.04	20.64		
2nd Cross road Left side		1.00	50.00	5.00	0.04	10.00		
3rd Cross road Left side		1.00	61.00	5.50	0.04	13.42		
2nd Cross Road Right side		1.00	62.00	6.50	0.04	16.12		
1st Cross Road Right side		1.00	60.00	6.50	0.04	15.60		
3rd Cross Road Right		1.00	60.00	5.00	0.04	12.00		
Cross Road		1.00	31.00	5.00	0.04	6.20		
4th Cross Right Side		1.00	48.00	5.00	0.04	9.60		
Cross Road		1.00	100.00	5.00	0.04	20.00		
Mathru Layout								
Main road		1.00	240.00	6.50	0.04	62.40		
1st Cross Road		1.00	52.00	5.50	0.04	11.44		
2nd Cross Road		1.00	14.80	5.50	0.04	3.26		
Basavalingappa Nagar								

Scanned by CamScanner

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	ain Road		1.00	318.00	5.20	0.04	66.14		
	2nd Cross Road		1.00	213.00	5.00	0.04	42.60		
	Cross Road-1		1.00	66.00	5.00	0.04	13.20		
	Cross Road-2		1.00	30.00	5.50	0.04	6.60		
	Cross Road-3		1.00	30.00	5.00	0.04	6.00		
							2901.14	**7831.4390**	**22720100.94**
	Approved rate	**7831.4390**					✓	✓	✓
18	Road marking with hot applied thermoplastic compound with reflectrising glass beads on bituminous surface / concrete surface : providing and laying of hot applied thermo plastic compound 2.5mm thick including reflectorising glass beads at 250gms per sqm area thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35 standards specified.complete as per specifications.								
		Sqm							
	Vijay Nagar Layout								
	5th Main Road From Entrance		2.50	596.00	0.15		223.50		
	4th Main Road From End		2.50	210.00	0.15		78.75		
	1st Cross Hasini Grand Appartment Road		2.50	136.00	0.15		51.00		
	2nd Cross M. Valarmathi Muniratnam #7		2.50	105.00	0.15		39.38		
	3rd Cross Sri Chowdeshawari Nilaya Laxmi Anjinappa # 25		2.50	85.00	0.15		31.88		
	4th Cross Amma Residency # 4		2.50	78.00	0.15		29.25		
	5th Cross #44 VR House		2.50	85.00	0.15		31.88		
	6th Cross Vaishnavi Beauty Care		2.50	60.00	0.15		22.50		
	3rd Main Road From End		2.50	540.00	0.15		202.50		
	Baba Nagar								
	2nd Main Road Near Hindustan Hardware		2.50	230.00	0.15		86.25		
	Shivapura Layout								
	Shiva parvathi Temple Road		2.50	220.00	0.15		82.50		
	Cross Road Sunrise Nest Appartment Beside Road		2.50	255.00	0.15		95.63		
	6th Cross Road		2.50	128.00	0.15		48.00		
	5th 'A' Cross Road		2.50	171.00	0.15		64.13		
	5th 'B' Cross Road		2.50	58.00	0.15		21.75		
	4th 'A' Cross Road		2.50	145.00	0.15		54.38		
	4th 'B' Cross Road		2.50	65.00	0.15		24.38		
	3rd 'A' Cross Road		2.50	47.00	0.15		17.63		
	3rd 'B' Cross Road		2.50	70.00	0.15		26.25		
	2nd 'A' Cross Road		2.50	48.00	0.15		18.00		
	2nd 'B' Cross Road		2.50	220.00	0.15		82.50		
	Cross Road		2.50	65.00	0.15		24.38		
	Chethan Nilaya # 41		2.50	62.00	0.15		23.25		
	1st 'A' Cross road		2.50	52.00	0.15		19.50		
	1st 'B' Cross Road		2.50	210.00	0.15		78.75		
	Srinivasa Hotel Road		2.50	64.00	0.15		24.00		
	Sunrise Nest Appartment Road		2.50	224.00	0.15		84.00		
	Muneshawara Layout								
	1st Main Road		2.50	96.00	0.15		36.00		
	4th 'A' Cross road		2.50	65.00	0.15		24.38		
	Kattigenahalli Govt School Road		2.50	54.00	0.15		20.25		
	3rd Main Road From End		2.50	102.00	0.15		38.25		
	3rd Cross Road From End		2.50	221.00	0.15		82.88		
	2nd Cross Road		2.50	228.00	0.15		85.50		
	2nd Main Road From 4th Cross		2.50	75.00	0.15		28.13		
	1st Cross Road From end		2.50	220.00	0.15		82.50		
	Main Road		2.50	188.00	0.15		70.50		
	Saptagiri Layout								
	Binod Electronics Road/ Arunpandit # 26 'A'		2.50	105.00	0.15		39.38		
	3rd B Cross								
	Sri Angenaiya Nilaya # 16,17		2.50	81.00	0.15		30.38		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Sri Chowdeshwari Nilaya Front Road #36		2.50	68.00	0.15		25.50		
Sri Chowdeshwari Nilaya Right Road #36		2.50	65.00	0.15		24.38		
Sri Laxmi Venkateshawara Nilaya # 58		2.50	65.00	0.15		24.38		
1st Main Road		2.50	105.00	0.15		39.38		
Anantam Nilaya # 42 & 43		2.50	98.00	0.15		36.75		
Someshawara Layout								
Sri Siddeshawara General Store Road		2.50	75.00	0.15		28.13		
Sri Ramanginaiya Nilaya # 9		2.50	130.00	0.15		48.75		
Gangothri Badavani								
1st Cross Road		2.50	55.00	0.15		20.63		
2nd Cross Road		2.50	65.00	0.15		24.38		
3rd Cross Road		2.50	72.00	0.15		27.00		
Poojappa Layout								
4th Cross Road		2.50	350.00	0.15		131.25		
Cross Road		2.50	80.00	0.15		30.00		
Muneshawara Swamy General Store		2.50	100.00	0.15		37.50		
Kempegowda Layout								
Main Road		2.50	185.00	0.15		69.38		
1st Main Road		2.50	145.00	0.15		54.38		
Cross Road-5		2.50	65.00	0.15		24.38		
Cross Road-4 Bilal Imam #103/17		2.50	192.00	0.15		72.00		
Cross Road -3 Guru Krupa # 40		2.50	94.00	0.15		35.25		
Cross Road -2		2.50	56.00	0.15		21.00		
Cross Road-1		2.50	95.00	0.15		35.63		
Kattigenahalli Main Road		2.50	860.00	0.15		322.50		
Dutta town ship								
Main Road		2.50	186.00	0.15		69.75		
2nd Cross Road SreeKaram Nilaya		2.50	40.00	0.15		15.00		
Cross Road-1		2.50	160.00	0.15		60.00		
Cross Road-2		2.50	120.00	0.15		45.00		
Cross Road at End		2.50	270.00	0.15		101.25		
Kuvempu Nagar 4th B Cross		2.50	85.00	0.15		31.88		
Anjanadri Layout								
2nd Cross Road		2.50	97.00	0.15		36.38		
Road Connecting 1 & 2nd Cross Roads		2.50	30.00	0.15		11.25		
1st Cross Road		2.50	110.00	0.15		41.25		
Agrahara Main Road (Thirumenahalli Lake)		2.50	240.00	0.15		90.00		
Thirumenahalli (Ward No-05)								
1st Cross Road		2.50	101.00	0.15		37.88		
2nd Cross Road		2.50	155.00	0.15		58.13		
MVM Sumo Institution Road		2.50	45.00	0.15		16.88		
Balaji Layout								
Pristine Woods Apartments		2.50	165.00	0.15		61.88		
Main Road		2.50	295.00	0.15		110.63		
1st Cross road Left side		2.50	86.00	0.15		32.25		
2nd Cross road Left side		2.50	50.00	0.15		18.75		
3rd Cross road Left side		2.50	61.00	0.15		22.88		
2nd Cross Road Right side		2.50	62.00	0.15		23.25		
1st Cross Road Right side		2.50	60.00	0.15		22.50		
3rd Cross Road Right		2.50	60.00	0.15		22.50		
Cross Road		2.50	31.00	0.15		11.63		
4th Cross Right Side		2.50	48.00	0.15		18.00		
Cross Road		2.50	100.00	0.15		37.50		
Mathru Layout								
Main road		2.50	240.00	0.15		90.00		
1st Cross Road		2.50	52.00	0.15		19.50		

Scanned by CamScanner

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
d Cross Road		2.50	14.80	0.15		5.55		
Basavalingappa Nagar								
Main Road		2.50	318.00	0.15		119.25		
2nd Cross Road		2.50	213.00	0.15		79.88		
Cross Road-1		2.50	66.00	0.15		24.75		
						4587.47	**459.2874**	**2106967.17**
Approved rate	**459.2874**							
							Modified Construction Cost	**93143381.16**
							Towards GST 12% of Modified Construction Cost	**11177205.74**
							Total	**104320586.89**
							Miscellaneous & Rounding Off	**5516.22**
							Approved Amount	**104326103.11**

Assistant Engineer
Byatarayanapura Sub Division
BBMP Bangalore

ಸಹಾಯಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

Asst. Executive Engineer
Byatarayanapura Sub Division
BBMP Bangalore

ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ
ಬಿ.ಬಿ.ಎಂ.ಪಿ., ಬೆಂಗಳೂರು-26

Executive Engineer
Byatarayanapura Division
BBMP Bangalore

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ,
ಬೃ.ಬೆ.ಮ.ಪಾ, ಬೆಂಗಳೂರು.

Technical Sanction
Accorded For R.C.104226103'D
Head of A/C P.31.58
CER NO : 19 **Dt:** 14.06.2022

Scanned by CamScanner